## 

**It's Artificial** 1, Lodge Farm Cottages, Preston Rd, Lytham Saint Annes FY8 5RW

01253 734607 sales@itsartificial.co.uk W www.itsartificial.co.uk

Т

E

| ECONOMY +                   |  |        |
|-----------------------------|--|--------|
| Туре                        | Tufted synthetic grass carpet  |        |
| Material                    | PE Monofilament straight & PP Monofilament curled (UV Stabilized)  |        |
| Yarn quality                | Environmental friendly, free of lead and cadmium   |        |
| Primary backing             | 100% PP black, UV Stabilized, Weight 180 gr/m <sup>2</sup>   |        |
| Secondary backing           | PP Eco Backing, Weight 300 gr/m <sup>2</sup>   |        |
| Waterpermeability           | 60 liter/min/m²  |        |
| Pile height                 | 20 mm  | ± 2 mm |
| Face weight                 | 1.398 gr/m²  | ± 10%  |
| Total weight                | 1.878 gr/m²  | ± 10%  |
| Tuft gauge                  | 5/16 gauge   |        |
| Stitches per 10 cm linear   | 30   | ± 1%   |
| Stitches per m <sup>2</sup> | 37.800   | ± 10%  |
| Colour                      | Mix of light and dark green + Field-Jute thatch  |        |
| UV stability                | Meets DIN 53387 Standard (6000 hours)  |        |
| Colour fastness             | Xenon Test: Blue Scale > 7, Grey-scale > 4   |        |
| Colour lining               | Not Applicable   |        |
| Roll width                  | 200 cm, 400 cm   |        |
| Roll length                 | 20-25m   |        |
| Applications                | Gardens, Landscaping, Terraces   |        |
| Infill advice               | Silica sand, gradation 0,5 - 1,0 mm, 80% roundshaped, appr. 3 - 4 kg/m2  |        |
| Comments                    | Before installation make sure the rolls are from the same production code (first 6 digits of the roll number) Project. |        |

